

Instructions to all concerned

as to

**BRINGING INTO USE NEW SIGNAL BOX AND UP
LOOP LINE BETWEEN REIGATE AND BETCHWORTH.**

Rules 77, 78, 79 and 80 to be observed. Drivers to keep a good look-out for hand signals.

BUCKLAND SIDING BOX

(between Reigate and Betchworth).

To be carried out on Sunday, 27th September, commencing at 8.0 a.m.

A new signal box, to be known as "Buckland Siding," communicating electrically with Reigate and Betchworth boxes and situated on the up side 1 mile, 5 yards from Reigate box and 1 mile, 1,385 yards from Betchworth box, will be brought into use for the operation of the new up loop line and points and signals referred to below.

Up loop line, to hold sixty wagons and an engine, situated on left hand side of up line, with facing points in up line 262 yards Betchworth side of signal box and trailing points in up line 339 yards Reigate side of signal box. The up line between these facing and trailing points will, in future, be known as the up main line.

Catch points in up loop line, 207 yards Betchworth side of signal box.

Facing points in up loop line leading to sand drag 26 yards long, 287 yards Reigate side of signal box.

Crossover road between down and up lines, 309 yards Betchworth side of signal box.

Trailing points in up loop line leading from Buckland Siding, 14 yards Betchworth side of signal box.

Down distant signal beneath Reigate down advanced starting signal, 1,439 yards from down home signal referred to in next paragraph. (During fog or falling snow a Fogsignalman will not be provided at this distant signal).

Down home signal, 15 feet high, on left hand side of down line, 269 yards Betchworth side of signal box.

Down starting signal, 15 feet high, on left hand side of down line, 835 yards from signal box.

Up distant signal, 15 feet high, on left hand side of up line, 1,085 yards from up home signals referred to in next paragraph. (During fog or falling snow a Fogsignalman will not be provided at this distant signal).

Up main home signal and up main to up loop ringed-arm home signal on half bracket post, 21 feet high, on left hand side of up line, 339 yards from signal box.